# Focused Air Quality Assessment Borrego Photovoltaic Solar Farm

MUP 09-012 (APN 141-230-26) MUP 09-014 (APN 141-230-33) Log No. ER. 09-09-05-001

## **Prepared for the:**

County of San Diego
Department of Planning and Land Use
Contact: Mark Slovick
5201 Ruffin Road, Suite B
San Diego, CA 92123
858-495-5172

## Prepared By:

Jeremy Louden

Lan Consulting, Inc.

446 Crestcourt Lane
Fallbrook, California 92028

## **Project Proponent:**

EE Borrego Land, LLC Contact: David Tomlinson 4660 La Jolla Village Drive, #460 San Diego, CA 92122

June 10September 23, 2010 (Revised)
December 17, 2009

Project: 0953-0708 Air Quality Report

# **TABLE OF CONTENTS**

TABLE OF	CONTENTS	II
LIST OF FI	IGURES	III
LIST OF TA	ABLES	III
ADDENIDI	x	
LIST OF A	CRONYMS	IV
EXECUTIV	/E SUMMARY	v
1.0 INT	RODUCTION	1
1.1	Purpose of this Study	1
1.2	Project Location	
1.3	Project Description	
2.0 EXIS	STING ENVIRONMENTAL SETTING	6
2.1	Existing Setting	6
2.2	CLIMATE AND METEOROLOGY	6
2.3	REGULATORY STANDARDS	6
2.3.1	Federal Standards and Definitions	6
2.3.2	STATE STANDARDS AND DEFINITIONS	8
2.3.3	REGIONAL STANDARDS	_
2.3.	CALIFORNIA ENVIRONMENTAL QUALITY ACT (CEQA) SIGNIFICANCE THRESHOLDS	
2.5	SDAPCD RULE 20.2 – AIR QUALITY IMPACT ASSESSMENT SCREENING THRESHOLDS	
2.6	LOCAL AIR QUALITY	12
3.0 ME	THODOLOGY	16
3.1	CONSTRUCTION EMISSIONS CALCULATIONS	16
3.2	Construction Assumptions	16
3.3	OPERATIONAL IMPACTS	17
4.0 FIN	DINGS	19
4.1	Construction Findings	19
4.2	HEALTH RISK	20
4.3	CONCLUSION OF FINDINGS.	21
E O CED	TIEICATIONS	22

# **List of Figures**

FIGURE 1-A: PROJECT VICINITY MAP
FIGURE 1-B: PROJECT SITE PLAN
FIGURE 1-C: EXISTING BORREGO SUBSTATION EXPANSION PLAN
FIGURE 2-A: AMBIENT AIR QUALITY MONITORING STATIONS WITHIN SDAB - CARB13
FIGURE 2–B: AMBIENT AIR QUALITY MONITORING STATIONS WITHIN SSAB – CARB14
<u>List of Tables</u>
TABLE 2.1: AMBIENT AIR QUALITY STANDARDS
TABLE 2.2: SAN DIEGO COUNTY AIR BASIN ATTAINMENT STATUS BY POLLUTANT11
TABLE 2.3: SCREENING THRESHOLD FOR CRITERIA POLLUTANTS12
TABLE 2.4: THREE-YEAR AMBIENT AIR QUALITY SUMMARY NEAR THE PROJECT SITE15
TABLE 3.1: EXPECTED CONSTRUCTION EQUIPMENT AND DURATIONS
TABLE 4.1: EXPECTED CONSTRUCTION EMISSIONS SUMMARY
<u>Appendix</u>
URBEMIS 2007
SCREEN 3
SCREEN 3

## **LIST OF ACRONYMS**

Photovoltaic (PV)

Mega Watt (MW)

Cubic Yards (CY)

Diesel Particulate Matter (DPM)

Miles Per Hour (MPH)

Decomposed Granite (d.g.)

San Diego Gas and Electric (SDG&E)

San Diego Air Basin (SDAB)

National Ambient Air Quality Standards (NAAQS)

California Ambient Air Quality Standards (CAAQS)

Office of Air Quality Planning and Standards (OAQPS)

Carbon Monoxide (CO)

Lead (Pb)

Nitrogen Dioxide (NO<sub>2</sub>)

Particulate Matter (PM<sub>10</sub> or PM<sub>2.5</sub>)

Ozone  $(O_3)$ 

Sulfur Dioxide (SO<sub>2</sub>)

Salton Sea Air Basin (SSAB)

Hydrogen Sulfide (H<sub>2</sub>S):

San Diego Air Pollution Control District (SDAPCD)

Regional Air Quality Strategy (RAQS)

Air Quality Impact Assessments (AQIA)

Volatile Organic Compounds (VOCs)

Toxic Air Contaminants (TACs)

Best Available Control Technology (T-BACT)

Polyvinyl Chloride (PVC)

Cubic Yard (CY)

#### **EXECUTIVE SUMMARY**

This air quality analysis has been completed to determine impacts, which may be associated with the construction and operation of the proposed photovoltaic (PV) solar farm. The Project would consist of two separate solar generation facilities on two individual parcels of land, with additional lands affected to allow for the transport of power generated to the existing Borrego Substation. The Project is located in the unincorporated community of Borrego Springs in eastern portion of San Diego County, CA.

The project proposes to grub and grade the site and move roughly 107,000 Cubic Yards (CY) of soil and then install the photovoltaic array. The transmission lines will installed extending from the 288-acre parcel to the existing Borrego Substation along one of two identified routes: 1) west from the northwesterly corner of the parcel within an existing 20-foot easement maintained by San Diego Gas and Electric (SDG&E) (overhead facilities); or, 2) south from the southwesterly corner of the parcel along an existing roadway to Palm Canyon Drive (underground), west along Palm Canyon Drive (overhead), then north along Borrego Valley Road (overhead). The Project will also install improvements at the Borrego Substation including a new 69 kV termination rack (bus bar), associated conductors and insulators, two breakers, two disconnect switches, and associated protection and control equipment. All phases of the proposed project are anticipated to be completed by the fall of 2011

During construction, the proposed project will produce fugitive dust and diesel particulate matter, Reactive Organic Gases, Oxides of Nitrogen, Carbon Monoxide and Sulfur Dioxide, however, only construction related PM10 without mitigation would be expected to exceed PM10 thresholds established by the County of San Diego. Implementation of mitigation activities described below will reduce construction emissions to below significance:

- 1. Apply water during grading/grubbing activities to all active disturbed areas at least twice daily.
- 2. Apply water to all onsite roadways at least three times daily or use of magnesium chloride or other County approved dust suppression additives and apply water one-time daily.
- 3. Reduce all construction related traffic speeds onsite to below 15 Miles per Hour (MPH).

A screening-level health risk assessment was conducted to determine the potential for the project to result in a significant impact on nearby sensitive receptors during short-term construction activities. For purposes of this analysis, the primary pollutant of concern is diesel particulate matter (DPM) which is emitted by the operation of heavy diesel equipment during construction activities. The result of the health risk assessment indicates that the proposed project will not result in a significant impact to nearby sensitive receptors.

Daily operations of the project will be primarily from maintenance and worker trips only and although emissions are expected, they would be minimal and would be below the screening level thresholds within the San Diego County Guidelines for Determining Significance.

Additionally, as part of the design all disturbed areas would be covered with gravel or a permeable soil binding agent to reduce dust once the project is constructed and operational. In order to control dust during the life of the project, a non-toxic, biodegradable agent or permeable rock material will be applied to all exposed surface areas. The binding agents would be suitable for both traffic and non-traffic areas. BindingPermeable binding agents such as PolyPavement require a single initial application and periodic maintenance every 2-3 years. These agents are biodegradable, eco-safe, liquid copolymers that stabilize and solidify soils or aggregates and facilitate dust suppression. Once applied to the soil, the copolymer molecules coalesce forming bonds between the soil particles remaining permeable to water. These materials are commonly used on non-paved service roads, golf course paths, dirt bike tracks, helicopter landing areas etc. Alternatively, a permeable rock material consisting of either river stone decomposed granite or gravel would placed in a thin cover over all exposed surface area.

#### 1.0 INTRODUCTION

# 1.1 Purpose of this Study

The purpose of this Air Quality study is to determine potential air quality impacts (if any) that may be created during the construction of a photovoltaic solar farm to be constructed near the town of Borrego Springs in eastern San Diego County. Should impacts be determined, the intent of this study would be to recommend suitable mitigation measures, which would reduce those impacts to levels that are less than significant. Daily operations of the project will be primarily from maintenance and worker trips, although some emissions are expected, they would be minimal and below the screening level thresholds within the San Diego County Guidelines for Determining Significance.

# 1.2 Project Location

The Project is located within the community of Borrego Springs, California in northeastern San Diego County. Eurus Energy America Corporation's wholly owned subsidiary, EE Borrego Land LLC proposes to develop such facilities to allow for the long-term generation of clean energy from solar power that would ultimately be sold and distributed for public consumption.

The Project would consist of two separate solar generation facilities on two individual parcels of land, with additional lands affected to allow for transport of the power generated to the existing Borrego Substation. The County Assessor Parcel Numbers (APNs) affected by the proposed Project for the main facilities include 141-230-26 (approximately 288 acres) and a portion of 141-230-33 (approximately 53 acres - to be leased by the Project proponent). Access to the 288-acre parcel and 53-acre lease parcel will be provided from Palm Canyon Drive via an existing 12- to 16-foot wide decomposed granite (d.g.) access road. A general project vicinity map is shown in Figure 1–A on Page 5.

# 1.3 Project Description

The proposed Project would result in the construction, operation and maintenance of a photovoltaic (PV) solar farm within the community of Borrego Springs, California in northeastern San Diego County. Eurus Energy America Corporation's wholly owned subsidiary, EE Borrego Land LLC and affiliates (herein referred to as Eurus

Energy) proposes to develop such facilities to allow for the long-term generation of clean energy from solar power that would ultimately be sold and distributed for public consumption.

The facilities will consist of an array of fixed-tilt, non-tracking solar PV panels, inverter/switching gear housed in 38 12-foot by 26.5-foot structures, one 20-foot by 30-foot storage shed, two onsite substations, and supporting transmission facilities. Energy generated will be transferred to the existing Borrego Substation, located approximately one mile to the west of the 288-acre parcel, adjacent to Borrego Valley Road, via a series of overhead transmission lines. The project site plan is provided in Figure 1-B on Page 6.

The transmission lines will extend from the 288-acre parcel to the Borrego Substation along one of two identified routes: 1) west from the northwesterly corner of the parcel within an existing 20-foot easement maintained by San Diego Gas and Electric (SDG&E) (overhead facilities); or, 2) south from the southwesterly corner of the parcel along an existing roadway to Palm Canyon Drive (underground), west along Palm Canyon Drive (overhead), then north along Borrego Valley Road (overhead). Project-related improvements at the existing Borrego Substation will occur in the area immediately to the south of the existing fenced facilities. Additionally, all existing access roads will covered with decomposed granite to reduce dust.

Utility poles will be placed at pre-determined intervals as needed for the transmission lines. Pole installation will be accomplished by advancement of holes into the soil using a truck mounted augers. Poles will then be raised to the vertical position and lowered into place. Alternatively, cement foundations will be installed and steel poles will be affixed to the cement foundations.

Project-related improvements at the Borrego Substation will consist of approximately 0.8 acres, and will include installation of a new 69 kV termination rack (bus bar), associated conductors and insulators, two breakers, two disconnect switches, and associated protection and control equipment. A "breakaway" perimeter fence 8 feet in height topped with one foot of barbed wire (similar to existing fencing around the Borrego Substation facilities) will be installed for security purposes. The proposed Borrego Substation expansion layout is provided in Figure 1-C on Page 7. It is anticipated that the project will be completed by the fall of 2011.

Co Hwy S22 De Anza Desert Country Club **Project** Location Anza-Borrego Desert State Wilderness Borrego Springs Borrego Valley Airport Club Circle Golf Course Desert Co Hwy S3 Lodge Source: Google Maps, 12/09 (78) Anza-Borrego

Figure 1-A: Project Vicinity Map

Palm Canyon Drive ( Proposed Gen-Tie Routes Existing Substation Expansion Borrego Valley Road Source: RBF Consulting, 4/10

Figure 1-B: Project Site Plan

0 SCALE: NTS WEST ELEVATION SCALE: NTS ,0t SDG&E BORREGO SUBSTATION PROPOSED EXPANSION AREA 0 PROPOSED OVERHEAD NORTHERN TRANSMISSION ROUTE 0 EXISTING DIRT ROAD 134. BREAKAWAY FENCE) DEAD END STRUCTURE (69kV HIGH VOLTAGE RACK WITH DISCONNECT SWITCH) PROPOSED 8' CHAINLINK BREAKAWAY FENCE WITH 3 STRAND BARB WIRE BUSBAR STRUCTURE (WITH DISCONNECT SWITCH) 200 PORTION OF EXISTING FENCE TO BE REMOVED EXISTING CHAINLINK FENCE (PORTION OF EXISTING SDG&E SUBSTATION EQUIPMENT PROPOSED OVERHEAD SOUTHERN TRANSMISSION ROUTE PROPOSED 69 KV EQUIPMENT AREA HIGH VOLTAGE BREAKER EXISTING STRUCTURE BORREGO VALLEY ROAD 5 ⊙ 6 0 4

Figure 1-C: Existing Borrego Substation Expansion Plan

## 2.0 EXISTING ENVIRONMENTAL SETTING

# 2.1 Existing Setting

The project site is comprised of two vacant lots with vegetation. No existing development was noted during our site visit.

## 2.2 Climate and Meteorology

Climate within the San Diego Air Basin SDAB area often varies dramatically over short geographical distances due to the size and topography. Most of southern California is dominated by high-pressure systems for much of the year, which keeps the desert mostly sunny and warm. Typically, during the winter months, the high pressure system drops to the south and brings cooler, moister weather from the north.

It is common for inversion layers to develop within high-pressure areas, which mostly define pressure patterns over the SDAB. These inversions are caused when a thin layer of the atmosphere increases in temperature with height. An inversion acts like a lid preventing vertical mixing of air through convective overturning.

# 2.3 Regulatory Standards

#### 2.3.1 Federal Standards and Definitions

The Federal Air Quality Standards were developed per the requirements of The Federal Clean Air Act, which is a federal law that was passed in 1970 and amended in 1990. This law provides the basis for the national air pollution control effort. An important element of the act included the development of national ambient air quality standards (NAAQS) for major air pollutants.

The Clean Air Act established two types of air quality standards otherwise known as primary and secondary standards. *Primary Standards* set limits for the intention of protecting public health, which includes sensitive populations such as asthmatics, children and elderly. *Secondary Standards* set limits to protect public welfare to include protection against decreased visibility, damage to animals, crops, vegetation and buildings.

The Environmental Protection Agency (EPA) Office of Air Quality Planning and Standards (OAQPS) has set National Ambient Air Quality Standards for principal pollutants, which are called "criteria" pollutants. These pollutants are defined below:

- 1. Carbon Monoxide (CO): is a colorless, odorless, and tasteless gas and is produced from the partial combustion of carbon-containing compounds, notably in internal-combustion engines. CO usually forms when there is a reduced availability of oxygen present during the combustion process. Exposure to CO near the levels of the ambient air quality standards can lead to fatigue, headaches, confusion, and dizziness. CO interferes with the blood's ability to carry oxygen.
- 2. Lead (Pb): is a potent neurotoxin that accumulates in soft tissues and bone over time. The major sources of lead emissions have historically been motor vehicles (such as cars and trucks) and industrial sources. Because lead is only slowly excreted, exposures to small amounts of lead from a variety of sources can accumulate to harmful levels. Effects from inhalation of lead near the level of the ambient air quality standard include impaired blood formation and nerve conduction. Lead can adversely affect the nervous, reproductive, digestive, immune, and blood-forming systems. Symptoms can include fatigue, anxiety, short-term memory loss, depression, weakness in the extremities, and learning disabilities in children.
- 3. **Nitrogen Dioxide (NO<sub>2</sub>):** is a reactive, oxidizing gas capable of damaging cells lining the respiratory tract and is one of the nitrogen oxides emitted from high-temperature combustion, such as those occurring in trucks, cars, power plants, home heaters, and gas stoves. In the presence of other air contaminants, NO<sub>2</sub> is usually visible as a reddish-brown air layer over urban areas. NO<sub>2</sub> along with other traffic-related pollutants is associated with respiratory symptoms, respiratory illness and respiratory impairment. Studies in animals have reported biochemical, structural, and cellular changes in the lung when exposed to NO<sub>2</sub> above the level of the current state air quality standard. Clinical studies of human subjects suggest that NO<sub>2</sub> exposure to levels near the current standard may worsen the effect of allergens in allergic asthmatics, especially in children.
- 4. Particulate Matter (PM<sub>10</sub> or PM<sub>2.5</sub>): is a complex mixture of tiny particles that consists of dry solid fragments, solid cores with liquid coatings, and small droplets of liquid. These particles vary in shape, size and chemical composition, and can be made up of multiple materials such as metal, soot, soil, and dust. PM<sub>10</sub> particles are 10 microns (μm) or less and PM<sub>2.5</sub> particles are 2.5 (μm) or less. These particles can contribute significantly to regional haze and reduction of visibility in California. Exposure to PM levels exceeding current air quality standards increases the risk of allergies such as asthma and respiratory illness.
- 5. Ozone  $(O_3)$ : is a highly oxidative unstable gas capable of damaging the linings of the respiratory tract. This pollutant forms in the atmosphere through reactions between chemicals directly emitted from vehicles, industrial plants, and many other sources. Exposure to ozone

- above ambient air quality standards can lead to human health effects such as lung inflammation, tissue damage and impaired lung functioning. Ozone can also damage materials such as rubber, fabrics and plastics.
- 6. **Sulfur Dioxide (SO<sub>2</sub>):** is a gaseous compound of sulfur and oxygen and is formed when sulfur-containing fuel is burned by mobile sources, such as locomotives, ships, and off-road diesel equipment. SO<sub>2</sub> is also emitted from several industrial processes, such as petroleum refining and metal processing. Effects from SO<sub>2</sub> exposures at levels near the one-hour standard include bronchoconstriction accompanied by symptoms, which may include wheezing, shortness of breath and chest tightness, especially during exercise or physical activity. Children, the elderly, and people with asthma, cardiovascular disease or chronic lung disease (such as bronchitis or emphysema) are most susceptible to these symptoms. Continued exposure at elevated levels of SO<sub>2</sub> results in increased incidence of pulmonary symptoms and disease, decreased pulmonary function, and increased risk of mortality.

#### 2.3.2 State Standards and Definitions

The State of California Air Resources Board (ARB) sets the laws and regulations for air quality on the state level. The California Ambient Air Quality Standards (CAAQS) are either the same as or more restrictive then the NAAQS and also restrict four additional contaminants. Table 2.1 on the following page identifies both the NAAQS and CAAQS. The additional contaminants as regulated by the CAAQS are defined below:

- 1. Visibility Reducing Particles: particles in the air that obstruct visibility.
- 2. **Sulfates**: are salts of Sulfuric Acid. Sulfates occur as microscopic particles (aerosols) resulting from fossil fuel and biomass combustion. They increase the acidity of the atmosphere and form acid rain.
- 3. **Hydrogen Sulfide** (H<sub>2</sub>S): is a colorless, toxic and flammable gas with a recognizable smell of rotten eggs or flatulence. H<sub>2</sub>S occurs naturally in crude petroleum, natural gas, volcanic gases, and hot springs. Usually, H<sub>2</sub>S is formed from bacterial breakdown of organic matter. Exposure to low concentrations of hydrogen sulfide may cause irritation to the eyes, nose, or throat. It may also cause difficulty in breathing for some asthmatics. Brief exposures to high concentrations of hydrogen sulfide (greater than 500 ppm) can cause a loss of consciousness and possibly death.
- 4. **Vinyl Chloride**: is also known as chloroethene and is a toxic, carcinogenic, colorless gas with a sweet odor. It is an industrial chemical mainly used to produce its polymer, polyvinyl chloride (PVC).

**Table 2.1: Ambient Air Quality Standards** 

		Ambient	Air Quality St	andards		
Pollutant	Average Time	Californ	ia Standards <sup>1</sup>		Federal Standards <sup>2</sup>	
		Concentration <sup>3</sup>	Method <sup>4</sup>	Primary <sup>3,5</sup>	Secondary <sup>3,6</sup>	Method <sup>7</sup>
Ozone (O <sub>3</sub> )	1 Hour	0.09 ppm (180 μg/m3)	Ultraviolet	-	Same as Primary	Ultraviolet Photometry
(-3,	8 Hour	0.070 ppm (137 μg/m3)	Photometry	0.075 ppm (147 μg/m3)	Standard	,
Respirable Particulate	24 Hour	50 μg/m3	Gravimetric or Beta	150 μg/m3	Same as	Inertial Separation
Matter (PM10)	Annual Arithmetic Mean	20 μg/m3	Attenuation	-	Primary Standard	and Gravimetric Analysis
Fine Particulate Matter	24 Hour	No Separat	e State Standard	35 μg/m3	Same as	Inertial Separation
PM2.5	Annual Arithmetic Mean	12 μg/m3	Gravimetric or Beta Attenuation	15 μg/m3	Primary Standard	and Gravimetric Analysis
	8 hour	9.0 ppm (10mg/m3)	Nan Disassina	9 ppm (10 mg/m3)	Nama	Non-Dispersive
Carbon Monoxide (CO)	1 hour	20 ppm (23 mg/m3)	Non-Dispersive Infrared Photometry (NDIR)	35 ppm (40 mg/m3)	None	Infrared Photometry
	8 Hour (Lake Tahoe)	6 ppm (7 mg/m3)	Friotometry (NDIK)	-	-	-
Nitrogen Dioxide (NO <sub>2</sub> )	Annual Arithmetic Mean	0.030 ppm (57 μg/m3)	Gas Phase	0.053 ppm (100 µg/m3)	Same as	Gas Phase
	1 Hour	0.18 ppm (339 μg/m3)	Chemiluminescence	0.100 ppm <sup>8</sup>	Primary Standard	Chemiluminescence
	Annual Arithmetic Mean	-		0.030 ppm (80 µg/m3)	-	
Cultur District (CO.)	24 Hour	0.04 ppm (105 µg/m3)	Ultraviolet	0.14 ppm (365 μg/m3)	-	Spectrophotometry (Pararosaniline
Sulfur Dioxide (SO <sub>2</sub> )	3 Hour	-	Fluorescence	-	0.5 ppm (1300 µg/m3)	Method)
	1 Hour	0.25 ppm (655 μg/m3)		-	-	-
	30 Day Average	1.5 μg/m3		-		-
Lead <sup>10</sup>	Calendar Quarter		Atomic Absorption	1.5 μg/m3	Same as Primary	High Volume Sampler and Atomic
	Rolling 3-Month Average			0.15 μg/m3	Standard	Absorption
Visibility Reducing Particles	8 Hour	Extinction coefficient of 0.23 per kilometer - visibility of ten miles or more (0.07 -30 miles or more for La				
Sulfates	24 Hour	25 μg/m3	Ion Chromatography			
Hydrogen Sulfide	1 Hour	0.03 ppm (42 μg/m3)	Ultraviolet Fluorescence			
Vinyl Chloride <sup>8</sup>	24 Hour	0.01 ppm (26 μg/m3)	Gas Chromatography			

- California standards for ozone, carbon monoxide (except Lake Tahoe), sulfur dioxide (1 and 24 hour), nitrogen dioxide, suspended particulate matter—PM10, PM2.5, and visibility reducing articles, are values that are not to be exceeded. All others are not to be equaled or exceeded. California ambient air quality standards are listed in the Table of Standards in Section 70200 of Title 17 of the California Code of Regulations.
- 2. National standards (other than ozone, particulate matter, and those based on annual averages or annual arithmetic mean) are not to be exceeded more than once a year. The ozone standard is attained when the fourth highest eight hour concentration in a year, averaged over three years, is equal to or less than the standard. For PM10, the 24 hour standard is attained when the expected number of days per calendar year with a 24-hour average concentration above 150 µg/m3 is equal to or less than one. For PM2.5, the 24 hour standard is attained when 98 percent of the daily concentrations, averaged over three years, are equal to or less than the standard. Contact U.S. EPA for further clarification and current federal policies.
- 3. Concentration expressed first in units in which it was promulgated. Equivalent units given in parentheses are based upon a reference temperature of 25°C and a reference pressure of 760 torr. Most measurements of air quality are to be corrected to a reference temperature of 25°C and a reference pressure of 760 torr; ppm in this table refers to ppm by volume, or micromoles of pollutant per mole of gas.
- 4. Any equivalent procedure which can be shown to the satisfaction of the ARB to give equivalent results at or near the level of the air quality standard may be used.
- 5. National Primary Standards: The levels of air quality necessary, with an adequate margin of safety to protect the public health.
- 6. National Secondary Standards: The levels of air quality necessary to protect the public welfare from any known or anticipated adverse effects of a pollutant.
- 7. Reference method as described by the EPA. An "equivalent method" of measurement may be used but must have a "consistent relationship to the reference method" and must be approved by the EPA.
- 8. To attain this standard, the 3-year average of the 98th percentile of the daily maximum 1-hour average at each monitor within an area must not exceed 0.100 ppm (effective January 22, 2010).
- 9. To attain this standard, the 3-year average of the 98th percentile of the daily maximum 1-hour average at each monitor within an area must not exceed 0.100 ppm (effective January 22, 2010).
- 10. National lead standard, rolling 3-month average: final rule signed October 15, 2008.

Source: California Air Resources Board (2/16/10)

## 2.3.3 Regional Standards

The State of California has 35 specific air districts, which are each responsible for ensuring that the criteria pollutants are below the NAAQS and CAAQS. Air basins that exceed either the NAAQS or the CAAQS for any criteria pollutants are designated as "non-attainment areas" for that pollutant. Currently, there are 15 non-attainment areas for the federal ozone standard and two non-attainment areas for the PM2.5 standard. The state therefore created the California State Implementation Plan (SIP), which is designed to provide control measures needed for California Air basins to attain ambient air quality standards.

The San Diego Air Pollution Control District (SDAPCD) is the government agency which regulates sources of air pollution within San Diego County. Currently, San Diego is in "non-attainment" status for O<sub>3</sub> and PM<sub>10</sub>. Therefore, the County of San Diego developed a Regional Air Quality Strategy (RAQS) to provide control measures to try to achieve attainment status as required for the SIP. The RAQS was adopted in 1991 and has been updated as recently as 2004. Criteria pollutant standards are generally attained when each monitor within the region has had no exceedances during the previous three calendar years. A complete listing of the current attainment status by pollutants for San Diego County is shown on Table 2.2 below.

# 2.3. California Environmental Quality Act (CEQA) Significance Thresholds

The California Environmental Quality Act has provided a checklist to identify the significance of air quality impacts. These guidelines are found in Appendix G of the CEQA guidelines and are as follows:

AIR QUALITY -- Where available, the significance criteria established by the applicable air quality management or air pollution control district may be relied upon to make the following determinations. Would the project:

- A: Conflict with or obstruct implementation of the applicable air quality plan?
- B: Violate any air quality standard or contribute substantially to an existing or project air quality violation?
- C: Result in a cumulatively considerable net increase of any criteria pollutant for which the project region is non-attainment under an applicable federal or state ambient air quality standard (including releasing emissions which exceed quantitative thresholds for ozone precursors)?
- D: Expose sensitive receptors to substantial pollutant concentrations?
- E: Create objectionable odors affecting a substantial number of people '?

Table 2.2: San Diego County Air Basin Attainment Status by Pollutant

S	an Diego County	Air Basin Attainment S	Status by Pollutant
Pollutant	Average Time	California Standards	Federal Standards
Ozone (O <sub>3</sub> )	1 Hour 8 Hour	Non-attainment	No Federal Standard Basic Non-attainment
Respirable Particulate Matter	Annual Arithmetic Mean 24 Hour	Non-attainment Non-attainment	No Federal Standard Unclassified <sup>1</sup>
(PM10) Fine Particulate Matter PM2.5	Annual Arithmetic Mean 24 Hour Annual Arithmetic Mean	No State Standard  No State Standard  Non-attainment	Unclassified <sup>2</sup> Attainment Attainment
Carbon Monoxide (CO)	8 hour 1 hour	Attainment	Maintenance Area <sup>3</sup>
Nitrogen Dioxide (NO <sub>2</sub> )	Annual Arithmetic Mean 1 Hour	No State Standard Attainment	Attainment No Federal Standard
Sulfur Dioxide (SO <sub>2</sub> )	Annual Arithmetic Mean 24 Hour 1 Hour	No State Standard Attainment Attainment	Attainment Attainment No Federal Standard
Lead	30 Day Average Calendar Quarter	Attainment No State Standard	No Federal Standard Attainment
Visibility Reducing Particles	8 Hour (10AM to 6PM, PST)	Unclassified	No Federal Standard
Sulfates Hydrogen Sulfide	24 Hour 1 Hour	Attainment Unclassified	No Federal Standard No Federal Standard

<sup>1.</sup> Data reflects status as of March 19, 2007.

# 2.5 SDAPCD Rule 20.2 – Air Quality Impact Assessment Screening Thresholds

The SDAPCD has established a threshold in Rule 20.2 for the preparation of Air Quality Impact Assessments (AQIA). These screening criteria can be used to demonstrate that a project's total emissions would not result in a significant impact as defined by CEQA. Should emissions be found to exceed these thresholds, additional modeling is required to demonstrate that the project's total air quality impacts are below the state and federal ambient air quality standards. These screening thresholds for construction and daily operations are shown in Table 2.3 below.

Non Criteria pollutants such as Hazardous Air Pollutants (HAPs) or Toxic Air Contaminants (TACs) are also regulated by the San Diego Air Pollution Control District (SDAPCD). Rule 1200 (Toxic Air Contaminants - New Source Review) adopted on June 12, 1996, requires evaluation of potential health risks for any new, relocated, or modified emission unit which may increase emissions of one or more toxic air contaminants. The rule requires that projects that propose to increase

<sup>2.</sup> Unclassified; indicates data are not sufficient for determining attainment or nonattainment.

<sup>3.</sup> Maintenance Area (defined by U.S. Department of Transportation) is any geographic region of the United States previously designated nonattainment pursuant t o the CAA Amendments of 1990 and subsequently redesignated to attainment subject to the requirement to develop a maintenance plan under section 175A of the CAA, as amended.

cancer risk to between 1 and 10 in one million need to implement toxics best available control technology (T-BACT) or impose the most effective emission limitation, emission control device or control technique to reduce the cancer risk. At no time shall the project increase the cancer risk to over 10 in one million.

This report assumes that Volatile Organic Compounds (VOC) and Reactive Organic Gases (ROG) are essentially the same due to the fact that emissions generated from the project represent non-methane organic compounds. Additionally, South Coast Air Quality Management District (SCAQMD) utilizes VOC standards.

**Table 2.3: Screening Threshold for Criteria Pollutants** 

Pollutant	Total Emissions (Pounds per Day)						
Co	onstruction Emissions						
Respirable Particulate Matter (PM <sub>10</sub> /PM <sub>2.5</sub> )	100/55						
Nitrogen Oxide (NO <sub>x</sub> )	250						
Sulfur Oxide (SO <sub>x</sub> )	250						
Carbon Monoxide (CO)	550						
Volatile Organic Compounds (VOCs)	75						
Reactive Organic Gases (ROGs)	75						

## 2.6 Local Air Quality

Criteria pollutants are measured continuously throughout the San Diego Air Basin (SDAB). This data is used to track ambient air quality patterns throughout the County. As mentioned earlier, this data is also used to determine attainment status when compared to the NAAQS and CAAQS.

The SDAPCD is responsible for monitoring and reporting monitoring data. The District operates 10 monitoring sites that collect data on criteria pollutants. Figure 2-A below shows the relative locations of the ambient monitoring stations. Additionally, because the project site is located on the northeastern edge of the SDAB adjacent to the Salton Sea Air Basin (SSAB), SSAB monitoring sites were also used to determine ambient air quality conditions. Figure 2-B on the following page shows the SSAB monitoring locations.

The proposed development project is closest to the SDAB site located in Alpine as well as the SSAB Westmorland monitoring site. Table 2.4 on Page 16 of this report identifies the criteria pollutants monitored at these stations.

FIGURE 2-A: Ambient Air Quality Monitoring Stations within SDAB - CARB




FIGURE 2-B: Ambient Air Quality Monitoring Stations within SSAB - CARB




Table 2.4: Three-Year Ambient Air Quality Summary near the Project Site

Pollutant	Closest Recorded Ambient Monitoring Site	Averaging Time	CAAQS	NAAQS	2006	2007	2008
O3 (ppm)	Westmorland- W 1st Street	1 Hour	0.09 ppm	-	0.10	0.10	0.10
	Westmorland- W 1st Street	8 Hour	0.070 ppm	0.075 ppm	0.09	0.09	0.09
PM10 (μg/m3)	Westmorland- W 1st Street	24 Hour	50 μg/m3	150 μg/m3	167	226	136
PM2.5 (μg/m3)	Alpine – Victoria Drive	24 Hour	-	35 μg/m3	N/A	41	37
	Alpine – Victoria Drive	Annual Arithmetic Mean	12 μg/m3	15 μg/m3	N/A	N/A	14
NO2 (ppm)	Alpine – Victoria Drive	Annual Arithmetic Mean	0.030 ppm	0.053 ppm	0.010	0.010	0.008
	Alpine – Victoria Drive	1 Hour	0.18 ppm	-	0.057	0.057	0.047

#### 3.0 METHODOLOGY

#### 3.1 Construction Emissions Calculations

Air quality impacts related to construction were calculated using the latest URBEMIS2007 air quality model, which was developed by ARB. URBEMIS2007 has been approved by SDAPCD and San Diego County for construction emission calculations. URBEMIS incorporates emission factors from the EMFAC2007 model for on-road vehicle emissions and the OFFROAD2007 model for off-road vehicle emissions. Default settings were used within the model.

Cancer Risk will be determined for Diesel Particulate Matter (DPM) at the point of maximum exposure. The SCREEN3 dispersion model can be used to determine the concentration for air pollutants at any location near the pollutant generator. Additionally, the model will predict the maximum exposure distance and concentration. Ldn Consulting utilized the worst case exhaust emissions generated from the Project from construction equipment as calculated within the URBEMIS2007 model. The worst case cancer risk if exposed to a DPM dose for 70 years is defined as:

$$CR_{DPM} = C_{DPM} \times URF_{DPM}$$

Where,  $CR_{DPM}$  = Cancer risk from diesel particulate matter (DPM) (probability on an individual developing Cancer

 $C_{DPM}$  = Annual average DPM concentration in  $\mu$ g/m3

 $URF_{DPM}$  = Unit risk factor is .0003 per continuous exposure of 1  $\mu g/m^3$  of DPM over 70-year period per person)

(Source: Health Risk Assessment Guidance for Analyzing Cancer Risks from Mobile Source Diesel Idling emissions for CEQA Air Quality Analysis (August 2003))

# 3.2 Construction Assumptions

The Project engineer expects to have rough grading complete in approximately nine weeks, trenching complete in approximately seven weeks and complete construction of the proposed project in ten months. This includes the 341 acres of onsite work and up to one-acre of additional work for both offsite improvements to the transmission/power lines and the required Borrego Substation infrastructure improvements. This assumption also includes all work necessary to provide onsite

access roads and the excavation and backfill for the footings for the photovoltaic panels were assumed in the trenching phase of the project. No grading activities are required for the existing site access road via Palm Canyon Drive. Table 3.1 on the following page shows the expected timeframes for the construction process at the Project location.

**Table 3.1: Expected Construction Equipment and Durations** 

Equipment Identification	Proposed Dates	Quantity	Load Factor	Hours per day
Mass Site Grading	10/1/2010 – 12/5/2010			
Dozer		3	.59	8
Graders		5	.61	8
Tractors/loaders/Backhoes		4	.55	8
Water Trucks		4	.50	8
Trenching	12/06/2010 - 01/26/2011			
Tractors/loaders/Backhoes		4	.55	8
Trenchers		2	.75	8
Water Trucks		1	.50	8
Building Construction	12/25/2010 - 08/01/2011			
Cranes		2	.56	8
Bore/Drill Rig		1	.75	8
Forklifts		1	.57	8
Generator		1	.74	8
Off Highway Trucks		4	.62	8
Tractor/loader/backhoe		5	.55	8
Welder		1	.45	8

This equipment list is based upon equipment inventory within URBEMIS2007. The quantity and types are based upon assumptions from projects of similar size and scope.

# 3.3 Operational Impacts

Daily operations of the project will be primarily from maintenance and worker trips only and although emissions are expected, they would be minimal and would be below the screening level thresholds within the San Diego County Guidelines for Determining Significance.

Additionally, as part of the design all disturbed areas would be covered with gravel or a <u>permeable soil</u> binding agent to reduce dust once the project is constructed and operational. In order to control dust during the life of the project, a non-toxic,

biodegradable agent or permeable rock material will be applied to all exposed surface areas. The binding agents would be suitable for both traffic and non-traffic areas. BindingPermeable binding agents such as PolyPavement require a single initial application and periodic maintenance every 2-3 years. These agents are biodegradable, eco-safe, liquid copolymers that stabilize and solidify soils or aggregates and facilitate dust suppression. Once applied to the soil, the copolymer molecules coalesce forming bonds between the soil particles remaining permeable to water. These materials are commonly used on non-paved service roads, golf course paths, dirt bike tracks, helicopter landing areas etc. Alternatively, a permeable rock material consisting of either river stone decomposed granite or gravel would placed in a thin cover over all exposed surface area. No further analysis has been conducted.

# 4.0 FINDINGS

# 4.1 Construction Findings

Construction analysis for the Project assumes that the contractor will utilize equipment in compliance with SDAPCD T/BACT requirements. Construction grading would take roughly nine weeks to complete, seven weeks for trenching activities and up to ten months for the entire Project to be completed, start to finish, including the upgrades to the offsite power line infrastructure. A summary of the construction emissions is shown in Table 4.1 below. Given these findings, PM10 emissions would exceed SDAPCD air quality standard of 100 lbs/day and would require mitigation to comply.

**Table 4.1: Expected Construction Emissions Summary** 

Year	ROG	NO <sub>x</sub>	СО	SO <sub>2</sub>	PM <sub>10</sub> (Dust)	PM <sub>10</sub> (Exhaust)	PM <sub>10</sub> (Total)	PM <sub>2.5</sub> (Dust)	PM <sub>2.5</sub> (Exhaust)	PM <sub>2.5</sub> (Total)
2010 (lb/day) Unmitigated	14.28	116.17	63.12	0	145.02	5.99	151.01	30.29	5.51	35.80
Significance Threshold (lb/day)	75	250	550	250	-	-	100	-	-	55
SDAPCD Impact?	No	No	No	No	-	-	Yes	-	-	Yes
2010(lb/day) Mitigated	14.28	116.17	63.12	0	62.8	5.99	68.79	13.12	5.51	18.63
Significance Threshold (lb/day)	75	250	550	250	-	-	100	-	-	55
SDAPCD Impact?	No	No	No	No	-	-	No	-	-	No
2011 (lb/day) Unmitigated	13.22	102.2	46.27	0	0.01	5.20	5.21	0	4.78	4.78
Significance Threshold (lb/day)	75	250	550	250	-	-	100	-	-	55
SDAPCD Impact?	No	No	No	No	-	-	No	-	-	No
2011 (lb/day) Mitigated	13.22	102.2	46.27	0	0.01	5.20	4.21	0	4.78	4.78
Significance Threshold (lb/day)	75	250	550	250	-	-	100	-	-	55
SDAPCD Impact Unmitigated?	No	No	No	No	-	-	Yes	-	-	No
SDAPCD Impact Mitigated?	No	No	No	No	-	-	No	-	-	No

It was found that the following mitigation measures would be required to reduce PM10 impacts to a level below significance:

- 1. Apply water during grading/grubbing activities to all active disturbed areas at least twice daily.
- 2. Apply water to all onsite roadways at least three times daily or use of magnesium chloride or other County approved dust suppression additives and apply water one-time daily.
- 3. Reduce all construction related traffic speeds onsite to below 15 Miles per Hour (MPH).

The above mitigation recommendations are based on control efficiencies established by SCAQMD CEQA air quality handbook and recommended within the URBEMIS 2007 air quality model. The CEQA handbook states that watering twice daily can reduce PM10 from 34-68% however; LDN Consulting utilized an average 51%.

### 4.2 Health Risk

Based upon this air quality modeling, we find that worst-case  $PM_{10}$  from exhaust could be as high 5.99 lbs per construction day (8-hours) or 0.0969 grams per second DPM during the construction day. Averaging this emission rate over the Project site area gives us the average emission rate for the Project area. Converting pounds (lbs) per day to grams per second is shown below:

$$\frac{5.99 \frac{lb}{day} * 453 \frac{grams}{lb}}{28,000 \frac{\sec onds}{Construction day}} = 0.0969 \frac{grams}{\sec ond}$$

The average emission rate over the grading area is 7.024x10<sup>-8</sup> g/m<sup>2</sup>/s, which was calculated as follows:

$$\frac{0.0969 \frac{grams}{\text{sec ond}}}{341acres * 4,046 \frac{meters^2}{acre}} = 7.024 * 10^{-8} \frac{grams}{\frac{meters^2}{\text{sec ond}}}$$

Utilizing the SCREEN3 dispersion model, we find that the peak maximum 1-hr concentration is 9.195  $\mu g/m^3$  during grading at a distance of roughly 833 meters

from the centroid of the Project site. This concentration would be lowered at any other distance from the project site. Utilizing the risk equation identified in Chapter 3 we calculate that the cancer risk over a 70-year continuous dose would be:

$$CR_{DPM-70vr dose} = 0.0003 \times 9.195 = 2.76 \times 10^{-3}$$

Based on these calculations, The Project is expected to generate maximum DPM during grading of the project, which is expected to take approximately ten months with workdays of eight hours per day during a typical five-day week. This would work out to 71-24 hr days out of 70 years or 71/25,550 or .0028 times the CR<sub>DPM</sub>. If one million people were exposed to the maximum DPM for the duration of grading at 833 meters from the project site, the estimated increased cancer risk could be:

$$0.0028 \times .002758 \times 1,000,000 = 7.724$$
 individuals per million

The numerical number of individuals exposed to DPM of this concentration from the project would be less than ten in one million. Therefore, no impacts are expected. No mitigation would be necessary. The SCREEN3 dispersion model outputs are attached to this report.

# 4.3 Conclusion of Findings

Based upon our analysis of construction activities for the proposed Borrego PV Solar Farm,  $PM_{10}$  impacts are expected during the construction phase of the Project if mitigation measures are not employed. The following mitigation requirements will be required to reduce construction related impacts to a level below significance:

- 1. Apply water during grading/grubbing activities to all active disturbed areas at least three times daily.
- 2. Apply water to all onsite roadways at least three times daily or use of magnesium chloride or other County approved dust suppression additives and apply water one-time daily.
- 3. Reduce all construction related traffic speeds onsite to below 15 Miles per Hour (MPH).

## 5.0 CERTIFICATIONS

The contents of this report represent an accurate depiction of the air quality environment and impacts within and surrounding the Borrego Photovoltaic Solar Farm development. The report was prepared by Jeremy Louden; a County approved CEQA Consultant for Air Quality.

Jeremy Louden

<u>2010</u>

Principal

Ldn Consulting, Inc.

Date

June 10September 23,

# **ATTACHMENT A**

URBEMIS 2007

4/11/2010 3:25:26 PM

### Urbemis 2007 Version 9.2.4

### Combined Winter Emissions Reports (Pounds/Day)

File Name: C:\Urbemis\Borregopvfarm.urb924

Project Name: 35mw Borrego

Project Location: California State-wide

On-Road Vehicle Emissions Based on: Version: Emfac2007 V2.3 Nov 1 2006

Off-Road Vehicle Emissions Based on: OFFROAD2007

#### Summary Report:

#### CONSTRUCTION EMISSION ESTIMATES

	ROG	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	PM10 Dust PM1	0 Exhaust	<u>PM10</u>	PM2.5 Dust	<u>PM2.5</u> Exhaust	PM2.5	<u>CO2</u>
2010 TOTALS (lbs/day unmitigated)	14.20	110.80	48.29	0.00	140.01	5.59	143.51	29.24	5.14	32.45	12,552.45
2010 TOTALS (lbs/day mitigated)	14.20	110.80	48.29	0.00	60.63	5.59	64.12	12.66	5.14	15.88	12,552.45
2011 TOTALS (lbs/day unmitigated)	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
2011 TOTALS (lbs/day mitigated)	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85

#### Construction Unmitigated Detail Report:

CONSTRUCTION EMISSION ESTIMATES Winter Pounds Per Day, Unmitigated

<u>ROG</u>	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	PM10 Dust	PM10 Exhaust	<u>PM10</u>	PM2.5 Dust	PM2.5 Exhaust	<u>PM2.5</u>	<u>CO2</u>
------------	------------	-----------	------------	-----------	--------------	-------------	------------	---------------	--------------	------------

Page: 2 4/11/2010 3:25:26 PM

Time Slice 8/2/2010-10/5/2010 Active Days: 47	8.07	64.69	33.73	0.00	<u>140.01</u>	3.49	<u>143.51</u>	<u>29.24</u>	3.21	<u>32.45</u>	6,293.81
Mass Grading 08/01/2010- 10/05/2010	8.07	64.69	33.73	0.00	140.01	3.49	143.51	29.24	3.21	32.45	6,293.81
Mass Grading Dust	0.00	0.00	0.00	0.00	140.00	0.00	140.00	29.24	0.00	29.24	0.00
Mass Grading Off Road Diesel	7.97	64.52	30.71	0.00	0.00	3.48	3.48	0.00	3.21	3.21	6,012.87
Mass Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Mass Grading Worker Trips	0.10	0.17	3.02	0.00	0.01	0.01	0.02	0.00	0.01	0.01	280.94
Time Slice 10/6/2010-10/22/2010 Active Days: 13	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching 10/06/2010-11/26/2010	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching Off Road Diesel	2.18	15.17	6.69	0.00	0.00	1.03	1.03	0.00	0.95	0.95	1,250.28
Trenching Worker Trips	0.07	0.12	2.20	0.00	0.01	0.01	0.02	0.00	0.00	0.01	204.32
Time Slice 10/25/2010-11/26/2010 Active Days: 25	<u>14.20</u>	<u>110.80</u>	<u>48.29</u>	0.00	0.01	<u>5.59</u>	5.60	0.00	<u>5.14</u>	5.15	<u>12,552.45</u>
Building 10/25/2010-06/01/2011	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Off Road Diesel	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Trenching 10/06/2010-11/26/2010	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching Off Road Diesel	2.18	15.17	6.69	0.00	0.00	1.03	1.03	0.00	0.95	0.95	1,250.28
Trenching Worker Trips	0.07	0.12	2.20	0.00	0.01	0.01	0.02	0.00	0.00	0.01	204.32

Page: 3

#### 4/11/2010 3:25:27 PM

Time Slice 11/29/2010-12/31/2010 Active Days: 25	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building 10/25/2010-06/01/2011	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Off Road Diesel	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Time Slice 1/3/2011-6/1/2011 Active Days: 108	<u>11.09</u>	<u>87.81</u>	<u>37.67</u>	0.00	0.00	<u>4.21</u>	<u>4.21</u>	0.00	3.87	<u>3.87</u>	<u>11,097.85</u>
Building 10/25/2010-06/01/2011	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
Building Off Road Diesel	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

#### Phase Assumptions

Phase: Mass Grading 8/1/2010 - 10/5/2010 - Grubbing and Mass Grading

Total Acres Disturbed: 323

Maximum Daily Acreage Disturbed: 7
Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

- 2 Graders (174 hp) operating at a 0.61 load factor for 8 hours per day
- 1 Rubber Tired Dozers (357 hp) operating at a 0.59 load factor for 8 hours per day
- 4 Tractors/Loaders/Backhoes (108 hp) operating at a 0.55 load factor for 8 hours per day
- 4 Water Trucks (189 hp) operating at a 0.5 load factor for 8 hours per day

Phase: Trenching 10/6/2010 - 11/26/2010 - ligth trenching

Off-Road Equipment:

5 Tractors/Loaders/Backhoes (108 hp) operating at a 0.55 load factor for 0 hours per day

#### 4/11/2010 3:25:27 PM

- 2 Trenchers (63 hp) operating at a 0.75 load factor for 8 hours per day
- 1 Water Trucks (189 hp) operating at a 0.5 load factor for 8 hours per day

Phase: Building Construction 10/25/2010 - 6/1/2011 - Construction of PV systems Off-Road Equipment:

- 1 Bore/Drill Rigs (291 hp) operating at a 0.75 load factor for 8 hours per day
- 2 Cranes (399 hp) operating at a 0.43 load factor for 7 hours per day
- 1 Forklifts (145 hp) operating at a 0.3 load factor for 8 hours per day
- 1 Generator Sets (49 hp) operating at a 0.74 load factor for 8 hours per day
- 4 Off Highway Trucks (479 hp) operating at a 0.57 load factor for 8 hours per day
- 5 Tractors/Loaders/Backhoes (108 hp) operating at a 0.55 load factor for 7 hours per day
- 1 Welders (45 hp) operating at a 0.45 load factor for 8 hours per day

#### Construction Mitigated Detail Report:

CONSTRUCTION EMISSION ESTIMATES Winter Pounds Per Day, Mitigated

	ROG	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	PM10 Dust	PM10 Exhaust	<u>PM10</u>	PM2.5 Dust	PM2.5 Exhaust	<u>PM2.5</u>	<u>CO2</u>
Time Slice 8/2/2010-10/5/2010 Active Days: 47	8.07	64.69	33.73	0.00	<u>60.63</u>	3.49	<u>64.12</u>	<u>12.66</u>	3.21	<u>15.88</u>	6,293.81
Mass Grading 08/01/2010- 10/05/2010	8.07	64.69	33.73	0.00	60.63	3.49	64.12	12.66	3.21	15.88	6,293.81
Mass Grading Dust	0.00	0.00	0.00	0.00	60.61	0.00	60.61	12.66	0.00	12.66	0.00
Mass Grading Off Road Diesel	7.97	64.52	30.71	0.00	0.00	3.48	3.48	0.00	3.21	3.21	6,012.87
Mass Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Mass Grading Worker Trips	0.10	0.17	3.02	0.00	0.01	0.01	0.02	0.00	0.01	0.01	280.94

Page: 5

Time Slice 10/6/2010-10/22/2010 Active Days: 13	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching 10/06/2010-11/26/2010	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching Off Road Diesel	2.18	15.17	6.69	0.00	0.00	1.03	1.03	0.00	0.95	0.95	1,250.28
Trenching Worker Trips	0.07	0.12	2.20	0.00	0.01	0.01	0.02	0.00	0.00	0.01	204.32
Time Slice 10/25/2010-11/26/2010 Active Days: 25	<u>14.20</u>	<u>110.80</u>	<u>48.29</u>	0.00	0.01	<u>5.59</u>	5.60	0.00	<u>5.14</u>	5.15	<u>12,552.45</u>
Building 10/25/2010-06/01/2011	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Off Road Diesel	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Trenching 10/06/2010-11/26/2010	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching Off Road Diesel	2.18	15.17	6.69	0.00	0.00	1.03	1.03	0.00	0.95	0.95	1,250.28
Trenching Worker Trips	0.07	0.12	2.20	0.00	0.01	0.01	0.02	0.00	0.00	0.01	204.32
Time Slice 11/29/2010-12/31/2010 Active Days: 25	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building 10/25/2010-06/01/2011	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Off Road Diesel	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Time Slice 1/3/2011-6/1/2011 Active Days: 108	<u>11.09</u>	<u>87.81</u>	<u>37.67</u>	<u>0.00</u>	0.00	<u>4.21</u>	<u>4.21</u>	0.00	3.87	<u>3.87</u>	<u>11,097.85</u>
Building 10/25/2010-06/01/2011	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
Building Off Road Diesel	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

#### 4/11/2010 3:25:27 PM

#### Construction Related Mitigation Measures

The following mitigation measures apply to Phase: Mass Grading 8/1/2010 - 10/5/2010 - Grubbing and Mass Grading

For Soil Stablizing Measures, the Water exposed surfaces 2x daily watering mitigation reduces emissions by:

PM10: 51% PM25: 51%

For Unpaved Roads Measures, the Reduce speed on unpaved roads to less than 15 mph mitigation reduces emissions by:

PM10: 44% PM25: 44%

For Unpaved Roads Measures, the Manage haul road dust 3x daily watering mitigation reduces emissions by:

PM10: 61% PM25: 61%

4/11/2010 3:25:04 PM

### Urbemis 2007 Version 9.2.4

### Combined Summer Emissions Reports (Pounds/Day)

File Name: C:\Urbemis\Borregopvfarm.urb924

Project Name: 35mw Borrego

Project Location: California State-wide

On-Road Vehicle Emissions Based on: Version: Emfac2007 V2.3 Nov 1 2006

Off-Road Vehicle Emissions Based on: OFFROAD2007

#### Summary Report:

#### CONSTRUCTION EMISSION ESTIMATES

	ROG	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	PM10 Dust PM1	0 Exhaust	<u>PM10</u>	PM2.5 Dust	<u>PM2.5</u> Exhaust	PM2.5	<u>CO2</u>
2010 TOTALS (lbs/day unmitigated)	14.20	110.80	48.29	0.00	140.01	5.59	143.51	29.24	5.14	32.45	12,552.45
2010 TOTALS (lbs/day mitigated)	14.20	110.80	48.29	0.00	60.63	5.59	64.12	12.66	5.14	15.88	12,552.45
2011 TOTALS (lbs/day unmitigated)	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
2011 TOTALS (lbs/day mitigated)	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85

#### Construction Unmitigated Detail Report:

CONSTRUCTION EMISSION ESTIMATES Summer Pounds Per Day, Unmitigated

<u>ROG</u>	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	PM10 Dust	PM10 Exhaust	<u>PM10</u>	PM2.5 Dust	PM2.5 Exhaust	<u>PM2.5</u>	<u>CO2</u>
------------	------------	-----------	------------	-----------	--------------	-------------	------------	---------------	--------------	------------

Page: 2 4/11/2010 3:25:04 PM

Time Slice 8/2/2010-10/5/2010	8.07	64.69	33.73	0.00	<u>140.01</u>	3.49	<u>143.51</u>	<u>29.24</u>	3.21	<u>32.45</u>	6,293.81
Active Days: 47 Mass Grading 08/01/2010- 10/05/2010	8.07	64.69	33.73	0.00	140.01	3.49	143.51	29.24	3.21	32.45	6,293.81
Mass Grading Dust	0.00	0.00	0.00	0.00	140.00	0.00	140.00	29.24	0.00	29.24	0.00
Mass Grading Off Road Diesel	7.97	64.52	30.71	0.00	0.00	3.48	3.48	0.00	3.21	3.21	6,012.87
Mass Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Mass Grading Worker Trips	0.10	0.17	3.02	0.00	0.01	0.01	0.02	0.00	0.01	0.01	280.94
Time Slice 10/6/2010-10/22/2010 Active Days: 13	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching 10/06/2010-11/26/2010	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching Off Road Diesel	2.18	15.17	6.69	0.00	0.00	1.03	1.03	0.00	0.95	0.95	1,250.28
Trenching Worker Trips	0.07	0.12	2.20	0.00	0.01	0.01	0.02	0.00	0.00	0.01	204.32
Time Slice 10/25/2010-11/26/2010 Active Days: 25	<u>14.20</u>	<u>110.80</u>	48.29	0.00	0.01	<u>5.59</u>	5.60	0.00	<u>5.14</u>	5.15	<u>12,552.45</u>
Building 10/25/2010-06/01/2011	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Off Road Diesel	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Trenching 10/06/2010-11/26/2010	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching Off Road Diesel	2.18	15.17	6.69	0.00	0.00	1.03	1.03	0.00	0.95	0.95	1,250.28
Trenching Worker Trips	0.07	0.12	2.20	0.00	0.01	0.01	0.02	0.00	0.00	0.01	204.32

Page: 3

#### 4/11/2010 3:25:05 PM

Time Slice 11/29/2010-12/31/2010 Active Days: 25	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building 10/25/2010-06/01/2011	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Off Road Diesel	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Time Slice 1/3/2011-6/1/2011 Active Days: 108	<u>11.09</u>	<u>87.81</u>	<u>37.67</u>	0.00	0.00	<u>4.21</u>	<u>4.21</u>	0.00	<u>3.87</u>	3.87	<u>11,097.85</u>
Building 10/25/2010-06/01/2011	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
Building Off Road Diesel	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

#### Phase Assumptions

Phase: Mass Grading 8/1/2010 - 10/5/2010 - Grubbing and Mass Grading

Total Acres Disturbed: 323

Maximum Daily Acreage Disturbed: 7
Fugitive Dust Level of Detail: Default

20 lbs per acre-day

On Road Truck Travel (VMT): 0

Off-Road Equipment:

- 2 Graders (174 hp) operating at a 0.61 load factor for 8 hours per day
- 1 Rubber Tired Dozers (357 hp) operating at a 0.59 load factor for 8 hours per day
- 4 Tractors/Loaders/Backhoes (108 hp) operating at a 0.55 load factor for 8 hours per day
- 4 Water Trucks (189 hp) operating at a 0.5 load factor for 8 hours per day

Phase: Trenching 10/6/2010 - 11/26/2010 - ligth trenching

Off-Road Equipment:

5 Tractors/Loaders/Backhoes (108 hp) operating at a 0.55 load factor for 0 hours per day

#### 4/11/2010 3:25:05 PM

- 2 Trenchers (63 hp) operating at a 0.75 load factor for 8 hours per day
- 1 Water Trucks (189 hp) operating at a 0.5 load factor for 8 hours per day

Phase: Building Construction 10/25/2010 - 6/1/2011 - Construction of PV systems Off-Road Equipment:

- 1 Bore/Drill Rigs (291 hp) operating at a 0.75 load factor for 8 hours per day
- 2 Cranes (399 hp) operating at a 0.43 load factor for 7 hours per day
- 1 Forklifts (145 hp) operating at a 0.3 load factor for 8 hours per day
- 1 Generator Sets (49 hp) operating at a 0.74 load factor for 8 hours per day
- 4 Off Highway Trucks (479 hp) operating at a 0.57 load factor for 8 hours per day
- 5 Tractors/Loaders/Backhoes (108 hp) operating at a 0.55 load factor for 7 hours per day
- 1 Welders (45 hp) operating at a 0.45 load factor for 8 hours per day

#### Construction Mitigated Detail Report:

CONSTRUCTION EMISSION ESTIMATES Summer Pounds Per Day, Mitigated

	ROG	<u>NOx</u>	<u>CO</u>	<u>SO2</u>	PM10 Dust	PM10 Exhaust	<u>PM10</u>	PM2.5 Dust	PM2.5 Exhaust	<u>PM2.5</u>	<u>CO2</u>
Time Slice 8/2/2010-10/5/2010 Active Days: 47	8.07	64.69	33.73	0.00	<u>60.63</u>	3.49	<u>64.12</u>	<u>12.66</u>	3.21	<u>15.88</u>	6,293.81
Mass Grading 08/01/2010- 10/05/2010	8.07	64.69	33.73	0.00	60.63	3.49	64.12	12.66	3.21	15.88	6,293.81
Mass Grading Dust	0.00	0.00	0.00	0.00	60.61	0.00	60.61	12.66	0.00	12.66	0.00
Mass Grading Off Road Diesel	7.97	64.52	30.71	0.00	0.00	3.48	3.48	0.00	3.21	3.21	6,012.87
Mass Grading On Road Diesel	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Mass Grading Worker Trips	0.10	0.17	3.02	0.00	0.01	0.01	0.02	0.00	0.01	0.01	280.94

Page: 5

# 4/11/2010 3:25:05 PM

Time Slice 10/6/2010-10/22/2010 Active Days: 13	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching 10/06/2010-11/26/2010	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching Off Road Diesel	2.18	15.17	6.69	0.00	0.00	1.03	1.03	0.00	0.95	0.95	1,250.28
Trenching Worker Trips	0.07	0.12	2.20	0.00	0.01	0.01	0.02	0.00	0.00	0.01	204.32
Time Slice 10/25/2010-11/26/2010 Active Days: 25	<u>14.20</u>	<u>110.80</u>	<u>48.29</u>	0.00	0.01	<u>5.59</u>	5.60	0.00	<u>5.14</u>	5.15	<u>12,552.45</u>
Building 10/25/2010-06/01/2011	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Off Road Diesel	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Trenching 10/06/2010-11/26/2010	2.25	15.29	8.89	0.00	0.01	1.04	1.05	0.00	0.95	0.96	1,454.60
Trenching Off Road Diesel	2.18	15.17	6.69	0.00	0.00	1.03	1.03	0.00	0.95	0.95	1,250.28
Trenching Worker Trips	0.07	0.12	2.20	0.00	0.01	0.01	0.02	0.00	0.00	0.01	204.32
Time Slice 11/29/2010-12/31/2010 Active Days: 25	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building 10/25/2010-06/01/2011	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Off Road Diesel	11.95	95.51	39.40	0.00	0.00	4.55	4.55	0.00	4.19	4.19	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Time Slice 1/3/2011-6/1/2011 Active Days: 108	<u>11.09</u>	<u>87.81</u>	<u>37.67</u>	<u>0.00</u>	0.00	<u>4.21</u>	<u>4.21</u>	0.00	3.87	<u>3.87</u>	<u>11,097.85</u>
Building 10/25/2010-06/01/2011	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
Building Off Road Diesel	11.09	87.81	37.67	0.00	0.00	4.21	4.21	0.00	3.87	3.87	11,097.85
Building Vendor Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
Building Worker Trips	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

#### 4/11/2010 3:25:05 PM

#### Construction Related Mitigation Measures

The following mitigation measures apply to Phase: Mass Grading 8/1/2010 - 10/5/2010 - Grubbing and Mass Grading

For Soil Stablizing Measures, the Water exposed surfaces 2x daily watering mitigation reduces emissions by:

PM10: 51% PM25: 51%

For Unpaved Roads Measures, the Reduce speed on unpaved roads to less than 15 mph mitigation reduces emissions by:

PM10: 44% PM25: 44%

For Unpaved Roads Measures, the Manage haul road dust 3x daily watering mitigation reduces emissions by:

PM10: 61% PM25: 61%

# **ATTACHMENT B**

SCREEN 3

```
*** SCREEN3 MODEL RUN ***

*** VERSION DATED 96043 ***

0953-05
```

### SIMPLE TERRAIN INPUTS:

SOURCE TYPE = AREA EMISSION RATE (G/(S-M\*\*2)) = .692000E-07 SOURCE HEIGHT (M) = 3.0000 LENGTH OF LARGER SIDE (M) = 1169.0000 LENGTH OF SMALLER SIDE (M) = 1169.0000 RECEPTOR HEIGHT (M) = 2.0000 URBAN/RURAL OPTION = RURAL

THE REGULATORY (DEFAULT) MIXING HEIGHT OPTION WAS SELECTED. THE REGULATORY (DEFAULT) ANEMOMETER HEIGHT OF 10.0 METERS WAS ENTERED.

MODEL ESTIMATES DIRECTION TO MAX CONCENTRATION

BUOY. FLUX = .000 M\*\*4/S\*\*3; MOM. FLUX = .000 M\*\*4/S\*\*2.

\*\*\* FULL METEOROLOGY \*\*\*

\*\*\* SCREEN AUTOMATED DISTANCES \*\*\*
\*\*\* SCREEN AUTOMATED DISTANCES \*\*\*

\*\*\* TERRAIN HEIGHT OF 0. M ABOVE STACK BASE USED FOR FOLLOWING DISTANCES \*\*\*

DIST (M)	CONC (UG/M**3)	STAB	U10M (M/S)	USTK (M/S)		PLUME HT (M)	MAX DIR (DEG)
100. 200. 300. 400. 500. 600. 700. 800. 900. 1100. 1200. 1300. 1400. 1500. 1600. 1700. 2000. 2100. 2200. 2300. 2400. 2500. 2600. 2700. 2800.	6.640 7.037 7.407 7.668 8.010 8.336 8.649 8.948 8.250 7.330 6.643 6.102 5.668 5.320 5.029 4.782 4.568 4.380 4.212 4.062 3.925 3.800 3.686 3.582 3.486 3.398 3.317 3.243 3.173	; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ; ;	1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0	1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0 1.0	10000.0 10000.0 10000.0 10000.0 10000.0 10000.0 10000.0 10000.0 10000.0 10000.0 10000.0 10000.0 10000.0 10000.0	3.00 3.00 3.00 3.00 3.00 3.00 3.00 3.00	45. 45. 45. 45. 45. 45. 45. 45. 45. 45.
				Pa	age 1		

```
borrego screen 3 output.txt
                                             1.0 10000.0
                                                                           45.
  3000.
            3.107
                             6
                                    1.0
                                                                3.00
                                            1.0 10000.0

1.0 10000.0

1.0 10000.0

1.0 10000.0

1.0 10000.0
            2.831
                                                                3.00
  3500.
                                                                           45.
                             6
                                    1.0
                                                                           45.
  4000.
            2.618
                            6
                                    1.0
                                                                3.00
            2.441
2.290
  4500.
                             6
                                    1.0
                                                                3.00
                                                                           45.
  5000.
                             6
                                    1.0
                                                                3.00
                                                                           45.
            2.158
  5500.
                             6
                                    1.0
                                                                3.00
                                                                           45.
                                             1.0 10000.0
  6000.
            2.042
                            6
                                    1.0
                                                                3.00
                                                                           45.
                                   1.0
                                                                3.00
                                                                           45.
  6500.
            1.938
                             6
                                             1.0 10000.0
                            6
                                             1.0 10000.0
  7000.
            1.847
                                   1.0
                                                                3.00
                                                                           45.
                            6
  7500.
            1.765
                                    1.0
                                             1.0 10000.0
                                                                3.00
                                                                           45.
                                    1.0
                                                                3.00
  8000.
            1.693
                            6
                                             1.0 10000.0
                                                                           45.
                                             1.0 10000.0
1.0 10000.0
1.0 10000.0
1.0 10000.0
                                                                           45.
                            6
  8500.
            1.626
                                    1.0
                                                                3.00
  9000.
            1.563
                             6
                                    1.0
                                                                3.00
                                                                           45.
  9500.
            1.505
                             6
                                    1.0
                                                                3.00
                                                                           44.
 10000.
            1.451
                                                                3.00
                                                                           45.
                                    1.0
                             6
MAXIMUM 1-HR CONCENTRATION AT OR BEYOND
                                                    100. M:
            9.028
                                             1.0 10000.0
                                                                3.00
   828.
                                    1.0
                                                                           45.
```

\*\*\*\*\*\*\*\*

CALCULATION PROCEDURE	MAX CONC (UG/M**3)	DIST TO MAX (M)	TERRAIN HT (M)
STMPLE TERRATN	9.028	828.	0.

\*\*\*\*\*\*\*\*\*\*